



CONSENT CALENDAR AGENDA ITEM

DATE: *27 August 2018*
RE: *Waste Water Pump Station*
TO: *Port of Newport Board of Commissioners*
ISSUED BY: *Aaron Bretz, Director of Operations*

BACKGROUND

We requested bids on the replacement a pair of sewer pumps in South Beach. The replacement is on the approved capital improvements projects list. The current pumps were installed in the late 70's; only one of the original two pumps is currently operating. The other pump will not hold a prime, and we recently had to conduct repairs to keep the only working pump running.

DETAIL SUPPORTING

We heard from three local plumbing companies on the project. Two declined to bid, and the third entered a bid that was significantly under budget. Because of the current condition of the pumps, and the very competitive price we received along with two refusals to bid, I recommend approval of this work. We simplified the design of the replacements, which made the cost of the work less than what was budgeted.

ALTERNATE CONSIDERATIONS

Continuing to use the existing pumps would be more expensive than replacement. We could wait to get more bids, but given the competitive price we received and the condition of the existing pumps, My recommendation is to get the work going as soon as we possibly can.

BUDGET IMPLICATIONS

This work is in the FY 2018-19 budget.

RECOMMENDATION

I recommend that a Commissioner make a MOTION TO AUTHORIZE THE GM TO CONTRACT WITH WITH COAST RANGE EQUIPMENT AND REPAIR TO REPLACE THE LIFT STATION PUMPS IN THE SOUTH BEACH MARINA, NOT TO EXCEED \$11,071.64.

Coast Range Equipment and Repair

Ph. (541)265-4465 Fax. (541)265-3347

CCB#128944

Remit To: P.O. Box 1253

Newport, OR. 97365

Estimate

DATE	ESTIMATE #
8/13/2018	No.775

NAME / ADDRESS
PORT OF NEWPORT 600 S.E. BAY BLVD. NEWPORT, OR 97365

P.O. NO.	TERMS	FOB	PROJECT
	Net 30		

ITEM	DESCRIPTION	QTY	TOTAL
	Lift Station / South Beach Lift Station /Does Not Include Alternator Repair		
***PUMPS	Barnes Model 3SEV-DS / 2HP / 1PH / 230 volt / Double Seals / Cast Iron Impeller / 3" Discharge/ 1750 RPM	2	6,974.00
VALVES	3" Brass Check Valve	2	274.90
***VALVES	3" Brass Gate Valve	2	166.70
MISC. PARTS	3" loose ring Flang	2	47.64
PVC MISC.	3" Male adapter	6	78.00
PVC MISC.	3" Elbow Sced 80	4	70.40
PVC MISC.	3" Sched 80 pipe	40	160.00
MISC. PARTS	To alter discharge lines and build cover for exposed pipe	1	1,500.00
Labor	To install pumps / and connect electrical / Test Run	10	900.00
Labor Help	Same as above	10	500.00
Freight	Freight Approx (Wt. 170# each)	1	400.00

Thank You For The Oppurtunity To Bid On This Project,	TOTAL	\$11,071.64
---	--------------	-------------

SIGNATURE _____